

TENDER FORM FOR CIVIL REPAIR WIRK 2021-22
THE FAZILKA CO-OP SUGAR MILLS LTD.,FAZILKA

NAME OF CONTACTOR :-

S.N.	Description	QTY	Rate(RS.)
1	E/Work in excavation in fdns , trenches etc. in all kind of soils	20 CUM	
2	Dismantling brick work in cement	10 CUM	
3	Dismantling brick work in mud including loading & unloading	10 CUM	
4	P/Laying PCC 1:8:16 With brick ballst 40mm gauge	5 CUM	
5	1 st class brick work in 1:6 cement mortar in super structure	20CUM	
6	P/Laying DPC 40 mm thick	50SQM	
7	1 st class brick work in 1:6 cement mortar in fdns	10CUM	
8	Cement plaster 1:4/1:3/1:5 , cement mortar 12.5 mm thick	600SQM	
9	P/Laying Cement concrete 1:2:4 flooring 75mm thick	100SQM	
10	Dismantling of brick on edge soling	100SQM	
11	Brick on edge soling sand grouted including preparation of sub grade	100SQM	
12	Earth filling under roads/ floors including compaction	100SQM	
13	Laying RCC 1:2:4 In fdns	5 CUM	
14	Laying steel reinforcement for RCC work	100 KG	
15	Laying PCC 124 In fdns	5CUM	
16	Making brick blast from brick bats	10CUM	
17	White washing two coats	2000Sqm	
18	Colour washing two coats	2000Sqm	
19	Painting two coats of enamel paint on old work	200Sqm	
20	Centering and shuttering for RCC work	150SQM	

NOTE; The quantity of the work may increase or decrees at the time of order
TERMS AND CONDITIONS

- 1- The above rate are labour rates only.
- 2- Work will be done as per specification.
- 3- QTY. of work may increase or decrease by the mills.
- 4- Mill shall not be responsible for any injury/accident/death to the contractor or labour.
- 5- No extra carriage for any material will be paid.
- 6- If any other item mentioned above, done at side will be paid as per Pb. Govt. CSR rates
- 7- Work will be complete before start of the crushing season 2021-22.
- 8- 80% payment of the work done shall be made against running bills and 20% payment Shall be made after completion of jobs as per the recommendations of CE.
- 9- TDS will be deducted as per rule.
- 10- GST extra if applicable.

J.E (CIVIL)

CHIEF ENGINEER

GENERAL MANAGER